

NAME OF WORK: Repair to Guest House at B.A.S.U., Patna for the year 2019-2020.

Tender amount: ₹ 14,64,653 /-

Cost of BOQ: ₹ 2,500/-

Paid by D.D. No.....Date//.../20..... & Name of Bank

Name of Agency: _____

**OFFICE OF THE ESTATE OFFICE
BIHAR ANIMAL SCIENCES UNIVERSITY
(TENDER DOCUMENT)**

1. Sealed tenders on plain paper to be eventually drawn in U.E. Form 61 No. F2/K2/H will be received upto 15:00 hours upto 22.11.2019 through Speed Post only by the undersigned and will be opened in presence of the tenderers or their authorized agents.
2. The bill of quantity will be downloaded upto 17:00 hrs on or before 21.11.2019. There will be no sale on the date of receiving tender.
3. The tender documents downloaded from the website will be submitted with cost of B.O.Q in the form of Demand Draft in favour of **FINANCE COMPTROLLER, BIHAR ANIMAL SCIENCES UNIVERSITY, PATNA**. Tenders submitted without cost of B.O.Q. in the form of demand draft will be summarily rejected.
4. Tenderers are required to deposit Earnest money at the rate of ₹ 100/- for every 5000/- or part thereof of the amount of the Estimate. Earnest Money can be deposited in shape of Demand Draft, N.S.C., N.D.C., Post Office Saving Bank Deposit, Post Office Time Deposit duly pledged to **ESTATE OFFICER, BIHAR ANIMAL SCIENCES UNIVERSITY, PATNA**. The tenderers shall have to attach a copy of N.P.S.C., N.D.C., N.S.C., D.D., or Pass Book with their quotations otherwise these tenders may outright be rejected. N.S.C., N.D.C. D.D., of Pass Book furnished after the receipt of tender on specified date and time will in no case be entertained.
5. Tenderers shall quote their rates both in figures and words and amount worked out against each item of work and initial all corrections, over writings interpolations. Indefinite forms like estimated rates etc. should not be considered.
6. The percentage rates quoted by the contractors should be inclusive of all taxes royalties and other incidental charges (i.e. Labour Cess etc.). Maximum applicable percentage rate below estimated cost is 10(Ten) percent.
7. The Contractor should quote in their tender:
 - a. Period within which they can complete the work commencing from the date of written orders to commence the work.
 - b. The plants and machinery they possess for execution of works.
 - c. Experience, they have with details of works and its locations.
 - d. Certificate, if any about the capacity of doing work.
 - e. Technical staff, if they possess.
8. The Contractor should satisfy themselves fully about the nature and site of works before offering their tenders and plea of any ignorance afterwards shall not be considered.
9. Tender without Earnest Money or insufficient Earnest Money will be rejected and there will be no position on the body of C.S.
10. Contractors are required to furnish up to date Tax Clearance Certificate in respect of I.T. and S.T. along with their tenders for values of works or ₹ 10,000/- or, over ₹ 10,000/- in each every tender. In absence of these documents along with their tender they will have to submit the same or certificates of No. outstanding Liabilities of I.T. and S.T. from the respective department within 10 days from the date of requisition in a registered letter with A.D. failing which their tenders shall be outright rejected and their Earnest Money furnished with the tenders shall stands forfeited without any further intimation.
11. Amount of Estimate: ₹/-
Earnest Money: ₹/-
Time of Completion:/-
Conditional tenders may be rejected.



12. After approval of rates by the competent authority the contractor shall have to deposit the initial Security money in shape of D.D. or N.S.C. with days of the receipt of the written orders from Engineer I/C and execute agreement failing which his tender shall be rejected and Earnest Money forfeited.
13. Authority shall reserve the right to reject any or all the tenders or distribute the work to more than one contractor without assigning any reasons.
14. The claim for idle labours due to stoppage of work non supply of materials, drawing and designs or delay due to any other reasons shall not be entertained.
15. The Contractor shall arrange necessary site for accommodation and other facilities like medical aid etc. for this labours at his own cost and initiative as well as will comply with all labours rules prevalent in the locality.
16. The specification of work mentioned in B.O.Q. where not mentioned in that case S.B.C., P.W.D., will be followed during the progress of the work. In case of any difference of things not being clear the instructions of the Estate Officer shall be followed.
17. No claim shall be entertained due to fluctuation of rates of labour and materials at any time during completion of work.
18. Materials recoverable or non-recoverable directly issued to work shall be issued to the contractor on proper Hand Receipt. Recovery of the cost of materials shall be made for the gross quantity issued and not for the quantity consumed in the portion of the work billed for. If materials are obtained in excess of precise requirement, the recovery of the cost of such materials will be made at double the issue rate stipulated in agreement.
19. The contractor employing trucks for carriage of materials or other works shall comply with the rules of Motor Vehicles Act.
20. In the case of L.S. Tenders contractors should clearly write both in figures and words.
21. It will be obligatory on the part of the tenders to keep his tender open for a period of 6 months (180 days) from the date of opening of tender for acceptance.
22. The contractor should maintain the Repair / Renovation Work during the defect liability period from the date of completion of work.
23. "SITE ORDER BOOK":- with numbered pages and bearing the certificates of the Engineer In Charge of containing so much pages shall have to maintain by the contractor at the site of work, and it will have to be produced, if the E.I. or Inspecting officers desire for any instructions concerning the work. This shall be the property of the Department after completion of work.
24. No. work beyond agreement shall be executed by the contractor unless specifically ordered by the Engineer In Charge in writing on "SITE ORDER BOOK" and the claim for such work shall be submitted regularly in every month. If the claim is not received in the month to which it relates it will be treated as time barred and may be disallowed.
25. Registered contractors of Class-IV category of the P.W.D having satisfactory records of work will be allowed to tender for the work. The category of contractor should be appropriate as per prevailing state rules and PWD code.
26. The sealed tender(s) (with Tender Document for NIT Number marked on top of the envelope) should be sent through Speed Post only to mailing address

To,
Estate Office,
Bihar Animal Sciences University,
P.O. - Bihar Veterinary College Campus,
Patna-800 014.


Estate officer, 30/1/19

Bihar Animal Sciences university, Patna

Bill of Quantity for Repair to Guest House at B.A.S.U., Patna for the year 2019-2020

Estimated Cost :- Rs. 14,64,653=00

E.M. to be deposited :- ₹ 29300=00

Last Date of downloading tender paper:- 21.11.2019 upto 5:00 p.m.

Cost of B.O.Q :- ₹ 2500=00

Last Date of Receiving Tender :- 22.11.2019 upto 3:00 p.m.

Time of Completion :- 60 Days

Sl.No.	Item of Work	Quantity unit	Rate	Amount
(1). Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 meters lead. Of area 3 sqm and below				
15.13.1		20 no @	48.80 /each	₹ 976=00
(2). Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 meters lead:				
15.7.4		1.49 m ³ @	685.10 /m ³	₹ 1021=00
(3). Centring and shuttering including strutting,propping etc. and removal of form for.				
a. Lintels, beams, plinth bams, grids, bressumers and contilevers.				
5.9.4		3.53 m ² @	362.60 /m ²	₹ 1280=00
(4). Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
(i) <u>TMTC-415 8 mm dia</u>		13.37 kg @	77.40 /kg	₹ 1035=00
5.22.7 A				
(ii) <u>TMTC-500 12mm dia</u>		26.02 kg @	75.20 /kg	₹ 1957=00
5.22.7C				
(5). Reinforced cement concrete work in wall (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upt floor five level excluding cost of centring, shuttering, finishing and reinforcement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size				
5.3		0.38 m ³ @	5,258.20 /m ³	₹ 1998=00
(6). Brick work with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:6 (1 cement: 6 coarse sand) Extra for Brick work in superstructure above plinth level upto floor V				
6.1.14A + 6.3A		5.27 m ³ @	5,501.40 /m ³	₹ 28992=00
(7). 12 mm th.C.P. of mix (1:6) including all complete job				
13.11.4		58.22 m ² @	126.20 /m ²	₹ 7347=00
(8). Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.With cement mortar 1:4 (1cement: 4 coarse sand)				
14.1.2		130.30 m ² @	213.30 /m ²	₹ 27793=00



(9). Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.			
15.56	137.92 m ² @	17.90 /m ²	₹ 2469=00
(10). Providing & fixing Rabbit wire mesh in ceiling before plaster including all complete job code 1220			
	137.92 m ² @	45.40 /m ²	₹ 6262=00
(11). Welding by electric plant including transportation of electric welding plant at site etc. complete.			
10.22(b)	1500.00 cm. @	3.20 /cm.	₹ 4800=00
(12). 6 mm C.P. to ceiling of mix(1:4) including all complete job 13.24.2			
	137.92 m ² @	110.90 /m ²	₹ 15295=00
(13). Providing and fixing wire gauge shutters using stainless steel grade 304 wire gauge with wire of dia 0.5 mm and average width of aperture 1.4 mm in both directions for doors, windows and clerestory windows with necessary screws: 9.27.2			
	107.21 m ² @	2,597.10 /m ²	₹ 278435=00
(14). Renewing glass panes, with putty and nails wherever necessary: 14.5.1 Float glass panes weighing 10 kg/m ² (4mm thick			
	70.93 m ² @	620.30 /m ²	₹ 43998=00
(15). Providing and fixing following fittings			
9.63.1 Tower bolt 250x10 mm	15 no @	67.20 /each	₹ 1008=00
9.62.1 door bolts 300x16mm	24 no @	162.40 /each	₹ 3898=00
9.66.1 Oxidised m.s. handles 125 mm	16 no @	29.90 /each	₹ 478=00
9.58.2 M.S. Hinge 125x125x27x2.8 mm	48 no @	56.60 /each	₹ 2717=00
(16). Providing & fixing false ceiling at all heights with GRG (Glass FibreReinforced Gypsum) false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having moisture content less than 2%, humidity resistance of 99%, NRC 0.50 to 0.75 as per IS 8225:1987, Non combustible as per BS 476 (part 4)- 1970 and light reflectance of 85% (minimum) to be laid in true horizontal level suspended on interlocking metal T-Grid of hot dipped galvanised iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 15x32 mm of length 3000 mm, cross-T of size 15x32 mm of length 1200 mm and secondary intermediate cross-T of size 15x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape 26.26.1			
	92.91 m ² @	1,384.20 /m ²	₹ 128606=00

(17). Removing old tarfelting incl. all complete job as per direction of E/I OSR	546.51 m ² @	6.40 /m ²	₹ 3498=00
(18). Demolishing cement concrete including disposal of material within 50 metre lead: 1:3:6 or richer mix 15.2.1	10.930 m ³ @	807.20 /m ³	₹ 8823=00
(19). Providing and laying cement concrete in kerbs, steps and the like at or near ground level excluding the cost of centring, shuttering and finishing. 4.4.1 1:2:4 (1 Cement :2 coarse sand :4 grade stone aggregate 20 mm nominal size)	21.86 m ³ @	4151.40 /m ³	₹ 90750=00
(20). 12 mm cement plaster of mix1:4(1 cement: 4 coarse sand) providing and mixing water proofing material in proportion recommended by the manufacturers: 13.11.2+ 13.36.2	546.51 m ² @	146.50 /m ²	₹ 80064=00
(21). Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (Thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy , bottle green , black of any size as approved by Engineer-in-charge in skirting , risers of steps and dados over 12 mm thick bed of cement Motar 1:3(1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete. 11.36	74.62 m ² @	739.80 /m ²	₹ 55204=00
(22). Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. 15.23.1	128.32 m ² @	25.50 /m ²	₹ 3272=00
(23). Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of ist quality conforming to IS : 15622 of approved make in colours such shades except white , Ivory , Grey , Fume Red , Brown , laid on 20 mm thick Cement motar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete 11.38	24.23 m ² @	736.40 /m ²	₹ 17843=00

<p>(24). Providing and laying vitrified floor tiles in different sizes {thickness to be specified by the manufactruer) with water absorption's less than 0.08 % and conforming to IS : 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joint with white cement and matching pigments etc., complete <u>Size of Tile 60x60 cm</u></p>	11.41.2	104.06 m ² @	1,520.90 /m ²	₹ 158265=00
<p>(25). Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete. <u>Size of Tile 60x60 cm</u></p>	11.46.2	4.17 m ² @	1,141.60 /m ²	₹ 4760=00
<p>(26). Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size,approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups,including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Rajnagar plain white marble /Udaipur green marble/ Zebra block marble Area of slab upto 0.50 sqm</p>	8.2.1.1	2.95 m ² @	2,224.00 /m ²	₹ 6561=00
<p>(27). Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall :</p>	18.11.1	36.60 m @	256.00 /m	₹ 9370=00
<p>(28). Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.</p>	18.10.	24.00 m @	177.80 /m	₹ 4267=00
<p>a. 15 mm dia nominal bore</p> <p>b. 25 mm dia G.I. pipe</p>		15.00 m @	239.00 /m	₹ 3585=00
<p>(29). Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require :</p>	17.7.1	2 no @	2307.10 /each	₹ 4614=00



(30). Providing and fixing water closet squatting pan (Indian type W.C.pan) with 100 mm sand cast Iron P or S trap, 10 litre low fixtures complete, including cutting and making good the walls and level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and floors wherever required : White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests

17.1.1 1 no @ 3390.90 /each ₹ 3391=00

(31). Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I.brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :

17.3.2 4 no @ 4529.10 /each ₹ 18116=00

(32). Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity - White

17.18.1 5 no @ 860.40 /each ₹ 4302=00

(33). Providing and fixing following fittings

18.65	PTMT soap Dish Holder	10 no @	122.10 /each	₹ 1221=00
17.73.1	Towel rail 15 mm bore	10 no @	367.50 /each	₹ 3675=00
17.31	Mirror of superior glass	6 no @	741.90 /each	₹ 4451=00
18.53.1	C.P. brass angle valve	5 no @	512.90 /each	₹ 2565=00
18.52.1	C.P. brass stop cock (concealed)	5 no @	588.20 /each	₹ 2941=00
18.49	C.P. Bib cock	12 no @	401.40 /each	₹ 4817=00
18.56.2	PTMT pillar cock	8 no @	183.50 /each	₹ 1468=00
	Zet Pressure	4 no @	550.00 /each	₹ 2200=00

(34). Providing and fixing on wall face unplasticised-PVC pipes with accessories incl...job

12.78.2	110 mm dia PVC Pipe	48.00 m @	238.30 /m	₹ 11438=00
12.79.5.2	110 mm bend	8 no @	124.70 /each	₹ 998=00
12.79.3.2	110 mm tee	6 no @	183.10 each	₹ 1099=00
12.80.2	110 mm clip	24 no @	157.37 /each	₹ 3777=00

(35). Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repair scratches etc. complete

13.80 2,138.82 m² @ 8.10 /m² ₹ 17324=00

(36). Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.

13.80A.1 268.22 m² @ 82.80 /m² ₹ 22209=00

(37). Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade . including priming coat with cement primer

13.78.2 + 2,718.98 m² @ 58.90 /m² ₹ 160148=00
13.77.3

(38). Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)

13.46.1 1,113.94 m² @ 89.40 /m² ₹ 99586=00

(39). Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade: With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works

13.81.3+ 214.07 m² @ 75.50 /m² ₹ 16162=00
13.82.4

(40). Carriage of materials including all complete job


a. Sone Sand (Lead 45 Km.)	28.55 m ³ @	900.05 /m ³	₹ 25696=00
b. Stone Chips (Lead 110 Km.)	19.76 m ³ @	1,868.80 /m ³	₹ 36927=00
c. Bricks Lead (1+7) Km.	2,140 no. @	856.35 %0 no.	₹ 1833=00

(41). Extra cost of materials

a. Bricks	2,140 no. @	1,485.15 %0 no.	₹ 3178=00
b. Cement	272 bag @	14.30 /bag	₹ 3890=00

Total ₹ 1464653=00


Dy. Estate Officer
B.A.S.U., Patna


Estate Officer
B.A.S.U., Patna



Fill up Given Information

- (a) Detail of Earnest money :
(b) Registration No.\ :
(Certified copy to be enclosed)
(c) Income tax & sale tax clearance certificate :
(Certified copy to be enclosed)
(d) License issued by the labour Department :
(Certified copy to be enclosed)
(e) Detailed of documents attached :
(f) Name and Address of the Tenders :
(h) Signature of tenderer :
(i) Mobile No. :


I/ we execute the work at:-

- (I) Estimated / Analysed rates shown in the Bill of Quantities.
(II) (I) In word Percent above the rates shown in the bill of quantities
(II) In figure Percent above the rates shown in the bill of quantities
(III) (I) In word Percent below the rates shown in the bill of quantities
(II) In figure Percent below the rates shown in the bill of quantities

I/We will complete the work within month from the date of work order.

I/ We have read and fully understood the terms and condition of the state (P.W.D.) contract form F2 and the N.I.T. and special condition attached here with.

Name & full signature of the Tenderer


Estate Office
Bihar Animal Sciences University
Patna – 14

- 1) No. of Cutting
2) No. of over writing
3) Rate quoted


Estate Office
Bihar Animal Sciences University
Patna – 14

N.I.T. SPECIAL CONDITIONS

1. Rates quoted should be inclusive of all taxes, royalties carriage and all other incidental charges what so ever.
2. The contractor shall not stipulate any additional conditions in their tender for increase of rates due to increase in rate of taxation. Rly. Freight and etc.
3. The rates should be written in figures as well as in words in such a way that interpolation is not possible and total amount of each item should be written both in figures and words and total amount of each page will also indicate both in figures and words.
4. Taxes, Rly. Freight and incidental charges on materials and labour in respect of the contractor shall be payable by the contractor and University shall not entertain any claim whatsoever in this respect.
5. The tenderers should acquaint themselves with the work and working conditions of the site locality and no claim will be entertained on this issue.
6. Site of execution of the work will be available as soon as work is awarded. In case, it is not possible for the department to take the entire site available on the award of the work, the contractor will have to arrange his working programme accordingly.
7. The contractor's responsibility for the construction shall commence from the date of issue of work order
8. The contractor shall study the specification, drawings and design carefully before submitting the tender
9. The work will be executed according to the approved and sanctioned design and drawing from time to time which will be binding on the contractor. No claim for the changes or modification in drawing and design will be tenable.
10. Contractor shall have to keep in upto date account of materials at site and his stores shall be inspected and stock taking will be done as and when required by the supervising staff of the department. The contractor should arrange for such inspection and free access should be given to the Supervising staff for such check up.
11. Quantities mentioned in the bill of quantity are approximate and the same may increase or decrease.
12. No claim shall be entertained on the grounds of fluctuation of rate in labour and materials etc. in the market during the period of filling the tender and completion of work.
13. The contractor shall arrange for necessary site accommodation and other facilities for the labour and no claim for medical aid to labour or any other incidental charges shall be entertained.
14. No claim for idle labour due to non-supply or delayed supply of materials machinery, design etc. by the department will be entertained.
15. The contractor shall strictly follow the conditions laid down in the minimum wages act. He shall also comply with the labour laws as may be current and furnish information as required from time to time.
16. All materials brought to site by the motor vehicle, other than vehicles belonging to the contractor for this work, should be by public carrier vehicles. The carriage of such materials by Private carrier would be illegal and contractor will accordingly be responsible for employing private carrier instead of public carrier.
17. The motor vehicles rules should be followed by the contractor will also be responsible for infringement of traffic rules accident, damages to roads and culverts etc. No responsibility for all or any of the above things will rest with department.
18. The work shall be done according to the University specification. In respect of such items of work which is not covered by the University specification the specification laid down by the Superintending Engineer, South Bihar Circle shall be allowed which will be final and conclusive.
19. All R.C.C. as well as plain cement concrete work shall be machine mixed and vibrated properly and submerged with 2" constant head of water over horizontally laid concrete component and constant spray curing on verticals concrete complete as directed by Engineer In-charge.
20. All shuttering and centering materials shall be arranged and procured by the contractor at his own cost and shall consist of rigid and sound work and steel works not to deform or disturb as a sequel to the working of vibrator. A scaffolding materials shall also be procured and arranged by the contractor at his cost. In case of centering and shuttering of R.C.C. column only steel plates of requisite thickness shall be used in centering and shuttering and not the wooden planks, so as to give smooth surface.
21. No claim shall be entertained for cleaning and scraping rusts and normal elements from steel issued by the department.
22. All R.C.C. works shall be designed as per latest I.S. code of practice.
23. If during execution of work, any item which is provided in the bill of quantities is not required to be executed due to change of specification etc. the contractor will have no claim whatsoever if that item is not done through them.
24. The contractor shall get the samples of bricks, sand stone chips etc. approved by the Estate Officer before undertaking mass collection of the same. Sample of the approved quality of materials shall be kept in the custody for comparison later on when the contractor's supply is made during progress of the work.
25. For overall structural works except plastering clean and coarse sand shall be used. For plastering, clean and medium coarse sand shall be used and should be screened to 256 mesh in one square inch before used in work.
26. Flat iron, for making grills for window, hand rails for stair case etc. shall be procured by the tenderer himself.
27. All points of welding in grills etc. must be clean smooth and strong. The samples of grill shall be got approved by the Estate Officer before taking up mass manufacture.

28. After completion of work the building floor shall be thoroughly washed and cleaned. The ugly marks on glass panes shutters etc. shall be removed and damages made good. The works of paint cement etc. shall be removed and cleaned nicely at the contractor's cost.
29. The contractor shall remove all his surplus materials rubbish etc. and leave the site clean and tidy after levelling and dressing the premises of the works as directed by the Engineer In-charge and then the work shall be considered as complete.
30. The site should be cleaned of all rubbishes, levelled and dressing as directed by the Engineer In-charge and shall prepare for layout works. Engineer weeds stumps of trees if any shall be removed by the contractor at his cost before layout is taken up as directed by the Engineer I/C. The cost of masonry, labours and etc. are incidental expenditures in layout of the work and shall not constitute a claim for the same.
31. The arrangements and the cost of all the store shed, labour shed, tools scaffolding water supply arrangement electric supply and building accessories shall be borne by the contractor at his cost and nothing will rest with the department. The contractor shall also provide all facilities and medical aid to the labours employed, at his cost.
32. Any approach road necessary for carriage of building materials to site of work, will have to be constructed by the contractor at his own cost and no claim for the same will be entertained by the department.
33. The contractor shall keep at site such implements to cost the soundness of material etc. at site. Moulds for making concrete cubes, steel comes for slump test etc. shall be kept at site and the cost of making them shall be borne by the contractor and no claim for the same will be tenable. He shall also provide and mark all arrangements at his cost for collecting, preparing and forwarding required number of samples for test and analysis at such time and such places or places as directed by the Engineer I/C and full payment of R.C.C. work shall be made only on satisfactory test result.
34. The department will not hold itself responsible if the work has been stopped at any stage of progress due to reasons beyond the control of the department and no claim will be entertained for the same.
35. The Government materials issued to the contractor for the work shall be properly looked after and guarded against theft, pilferage and losses due to fire etc. and for such any loss, the responsibility shall entirely rest with the contractor.
36. The contractor shall comply sufficient number of skilled and experienced labours to the job in order to achieve proportionate time given for the work during, execution of work, if his any mason or labour is found avoiding instructions to follow, shall be turn out at once from the work site.
37. Good and approved quality of lime should be used and samples may be got approved before use in works.
38. In all R.C.C. and R.C.C. works, Pakur or Manpur stone chips and Coarse sand of specified size grade and quality confirming to the Indian standard specification no. 456-964 shall be used. The bricks to be used in all brick works shall confirm requirement of relevant I.S. Code.
39. The jamb and soffit of the door and windows openings should be smooth, true to plumb and suitable spaces will have to be left for receiving W.I. clamps as per direction of Engineer In- Charge for which no claim shall be entertained.
40. Procurement of water in all seasons with all leads and lift will rest with the contractor at his cost.
41. The N.I.T. special conditions and other condition attached with the bill quantity will form integral part of the contract document and should be duly signed by the tenderer on each page as taken of acceptance while submitting the tender for the work.
42. The contractor will be responsible for accident etc. if any during execution of work and nothing will rest with the department.
43. Suitable recess for fixing clamps for doors and window, Jali work and railings whenever required, shall have to be provided by the contractor in brick walls, R.C.C. columns and R.C.C. roof as per direction of Engineer I/C without any cost.
44. The Engineer in-charge will have full powers to inquire the removal, from the premises of the site, of all materials which in his opening are not in accordance with, specification and in case of default the Engineer. I/C is at liberty to sell such inferior material at the contractor's cost and risks.
45. The teak wood and Sal wood shall be well seasoned and free from dead knots and other timber defects for the manufacture of frames and shutters and should be got approved before use in the works.
46. Fittings and fixtures for doors and windows etc, shall be got approved by the Estate Officer well in advance before use in work. The approved fittings and fixtures shall be mounted on a wooden board and always kept at site of work open or inspection and one such mounted board will be deposited in the office of the Estate Officer at the contractors cost.
47. Where not otherwise specified 1/8" thick plain glass panes weighting 2400 per fit (now 7.5 Kg per sqm only) shall be used in all glazed shutter
48. The contractor shall offer all facilities to the departmental officers for supervision, taking measurements, checking of bills etc. and any damage so occurred in the process will be made good by the contractor at his own cost.
49. Where joints in reinforcements in all R.C.C. works cannot be avoided due to required length of steel bars, whether mild or for steel, they will be formed by over lapping to a length of 45 times the diameter and tied with 16.5 annaled soft iron wire.
50. During casting R.C.C. foundation, the foundation trenches shall be kept free from water and if necessary the water shall be pumped out for which no extra payment to contractor shall be paid.
51. In on account bills of the contractors, the maximum rate of any item of work for payment not included in the agreement, will be the BASU, Patna Schedule rates of work fixed time to time. In case BASU not having their own schedule of rates, the schedule rate of work of S.B./C., P.W.D. may be followed.

52. In case any item of work not covered by Bihar Animal Sciences University, Patna or P.W.D. / B.C.D schedule of rates may be paid as per actual analysis of rates obtained from the local market.


Estate officer

Bihar Animal Sciences University, Patna